PWG -71 EXTRA ITEM RATE LIST STATEMENT

Development of Dobbighat in Ward No.01

Client : Bruhat Bangalore Mahanagara palike

Agency K Lakshmi Narayan Reddy

Sl. No.	Item of Work	Unit	Approximate Quantity	Rate	Amount In Rs	Whether the items are alternative to items in the tender or whether they are additional items (If items are in lieu of some items in the accepted tender, such items should be metioned	Wherther the extra item is included in the sanctioned estimate	How the extra cost of the item is propposed to be met	Whether the extra item is included in the suchedule of rate of the Division. If so reference to this item of the schedule to be given , if not data sheets should accompany the rate list	Remarks
EIRL-1	Supplying UNPLASTICISED PVC pipes conforming to IS 16098:2013 with latest amendments ended with integral sockets with ISI mark and conveying to worksite, rolling and lowering into trenches, laying true to line and level and perfect linking at joints, testing and commissioning, including loading and unloading at both destinations and cuts of pipes wherever necessary including jointing of UPVC pipes (with cost of elastomeric sealing rings) and specials (excluding cost of specials) with jointing of approved type, with all labour, lead & lifts, including encasing the pipes alround to a depth of not less than 15 cms. with soft gravel or selected earth available from the excavation etc. complete and giving necessary hydraulic test to the required pressure as per ISS (contractor will make his own arrangements for	RMT	578.90	214.18	123988.57	Additional Item	No	in the savings of other items in the same estimate	Pg No.134 of Water supply And UGD S.R 2021-22	
EIRL-2	Refilling available earth around trenches/pipelines, cables in layers not exceeding 20 cms in depth, compacting each deposited layer by ramming after watering with a lead upto 50 m , and lift upto 1.5 m. Including cost of all labour complete as per specifications (KPWD SR 2021-22, Volume-I, Item No.1.10, Page No.7	Cum	277.87	140.90	39151.21	Additional Item	No	in the savings of other items in the same estimate	Pg No.7 of KPWD S.R 2021-22(V-I)	
	EIRL TOTAL				163139.78					

Total Amount of Sanctioned Tender	=	25431551.23	
Net Excess Amount of EIRL	=	163139.78	
Total % excess to the Tendered Amount	=	0.64	%

Assistant Engineer
Project Division

Assistant Executive Engineer
Project Division

Executive Engineer
Project Division